

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


28-15-26W

Company- EMPIRE DRILG. CO.
Farm- Harry Babcock No. 2

SEC. 28 T. 15 R. 26W
C SW NE

Total Depth. 4460'
Comm. 7-20-65 Comp. 8-1-65
Shot or Treated.
Contractor. Co. Tools.
Issued. 3-5-66

County Gove KANSAS



Elevation. 2527' KB

Production. Pmp. 180 BOPD, 12% W.

Figures Indicate Bottom of Formations.

Surface, shale	102
shale	980
shale, sand	1394
shale	1495
sand	1730
shale	1956
Anhydrite	1994
shale, shells	2160
shale	2328
salt	2437
shale	2470
lime, shale	3130
lime	3265
shale, lime	3790
lime	3848
lime, chert	3895
lime	4095
lime, shale	4310
lime, shale, sand	4381
Quartz, chert, sand,	
lime, shale	4405
Mississippi lime	4417
Mississippi dolomite	4460 RTD
Total Depth	

TOPS: SCHLUMBERGER

* Anhydrite(Sc)	1956
Waubensee	3372
Shawnee Group(Topeka)	3556
Queen Hill	3636
Heebner	3766
Toronto	3788
Lansing	3807
Muncie Creek	3959
B/Kansas City	4103
Pawnee	4203
Fort Scott	4246
Cherokee Group	4297
Conglomerate	4386
Mississippi lime	4406
Mississippi dolomite	4420