


WELL RECORD

28-15-26W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

API#15-063-20,124

640 Acres
N

Locate well correctly

Lease Name: Snodgrass "A" Well No. 1
 Well Located: C NW NW
Gove SEC 28 TWP 15S RGE 26W
 Operator: Pickrell Drilling Company
 Address: 705 Fourth National Bank Bldg., Wichita, Kansas
 Elevation: Ground 2430 D.F. 2432 K.B. 2435
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 6/24/ 1972 Drilling Completed: 7/6/ 1972
 Well Completed: 19 Total Depth 4358
 Initial Production: _____

Casing Record

Size: 8-5/8" Set at 250 Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record


Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>150</u>	<u>3/2 cement</u>
_____	_____	_____
_____	_____	_____

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____



Electric Log Run (Show type log and depths covered)

Great Guns - GR-N, Guard-Cal.

(Fill in formation and related information on reverse side)

Show Drill Stem Tests,
Well Stimulation and
Production Tests

28-15-26w

Formation	Top	Bottom	
Sandy Shale	0	130	DST # 1 3902-3935: Open 40" WB 15 mins. Rec. 30' mud
Shale & Shells	130	258	IBHP 1175#/30", FBHP 1102#/45", IFP 37#, FFP 42#.
Shale	258	1400	DST # 2 3935-3965: Open 2 hrs., Fair blow, Rec. 240'
Sand	1400	1630	muddy water, IBHP 1259#/30", FBHP 1154#/60",
Shale - Red Bed	1630	1869	IFP 31#, FFP 126#.
Anhydrite	1869	1905	DST # 3 4062-4130: Open 40 mins., weak blow 15".
Shale	1905	2230	Rec. 10' mud. IBHP 95#/30", FBHP 63#/45", IFP 52#,
Shale & Lime Stringers	2230	2530	FFP 52#.
Lime - Shale	2530	2640	DST # 4 4213-4261: Open 40 mins., Weak blow 15 mins.,
Shale - Lime	2640	3130	rec. 15' mud. No show. IBHP 1112#/30",
Shale	3130	3295	FBHP 1008#/45", IFP 42#, FFP 42#.
Shale & Sandy Lime	3295	3455	DST # 5 4330-4335: Open 1 hr. Weak blow 20 mins
Lime - Shale	3455	3560	Rec. 15' mud w/spots of oil. IBHP 924#/30"
Shale	3560	3670	FBHP 757#/60", IFP 44#, FFP 44#.
Lime & Shale	3670	3740	DST # 6 4335-4345: Open 40 mins., Weak blow 20 mins.
Lime	3740	3870	Rec. 15" VSOCM, IBHP 1091#/30", FBHP 1050#/60".
Lime & Shale	3870	3935	IFP 31#, FFP 21#.
Lime	3935	4060	DST # 7 4345-4358: Open 2 hrs., Strong blow. Rec.
Lime & Shale	4060	4130	10' clean oil, 1680' water. IBHP 1269#/30"
Lime	4130	4178	FBHP 1248#/60", IFP 73#, FFP 768#.
Lime & Shale	4178	4238	
Lime	4238	4278	
Lime & Conglomerate	4278	4329	
Missippian	4329	4357	
Lime, RTD	4357	4358	

LOG TOPS

SC	1870	MISS LM	4325
HEEB	3686	MISS DOL	4332
TOR	3707	TD	4358
LANS	3728		
KC	3892		
STARK	3970		
BKC	4025		
MARM	not reported		
FT SC	4234		
CHER	4260		
LONG	4309		

C.F.S.

3720	4030
3773	4130
3819	4261
3835	4335
3855	4345
3905	4358
3925	
3935	
4000	

Slope Tests

2000
2500
3000
3500
4000