KANSAS PL

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey


API No. 15 — 063 (County) — 20,515 (Number) WICHITA BRANCH

S. 25 T. 15 R. 27W E W

Loc. E/2 NE SW

County Gove

640 Acres



Locate well correctly

Elev.: Gr. 2435

DF 2441 KB 2443

Operator: Reach Petroleum Corporation	
Address: 3751 E. Douglas, Wichita, KS 67218	
Well No.: #1	Lease Name: Schepman
Footage Location: 1980 feet from (N) (S) line	2310 feet from (E) (W) line
Principal Contractor: Reach Drilling	Geologist: Dusty Rhoades
Spud Date: 6/19/81 / Date Completed: 6/29/81	Total Depth: 4360 / P.B.T.D.
Directional Deviation: None.	Oil and/or Gas Purchaser: D & A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"		298'	common	185	2% gel 3% CaCl

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION D & A

Date of first production	Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold):

Producing interval(s):

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Reach Petroleum Corporation		
Well No. #1	**Lease Name** Schepman	Dry Hole
S 25 T 15 R 27W E/W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Eagle	2773			
Onaga	2908			
Wabaunsee	2959			
Stotler	3096			
Heebner	3673			
Lansing	3715			
Hertha	3997			
Pawnee	4154			
Ft. Scott	4210			
Cherokee	4237			
Mississippian	4312			

DST#1, 3953-85', Swope, 30-30-30-30, Rec. 5' SOCM, IHP 2017 psi., IFP 39-39 psi., ISIP 59 psi., FFP 39-39 psi., FSIP 49 psi., FHP 2007 psi.

DST#2, 3987-4012', Hertha, 30-30-30-30, Rec. 5' Mud w/specks of oil, IHP 2027 psi., IFP 39-39 psi., ISIP 39 psi., FFP 39-39 psi., FSIP 39 psi., FHP 2017 psi.

DST#3, 4280-4317', Mississippian, 30-30-30-30, Rec. 5' OCM, IHP 2293 psi., IFP 30-30 psi., ISIP 752 psi., FFP 40-40 psi., FSIP 535 psi., FHP 2274 psi.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Michael R. Bryan
Signature

Michael R. Bryan, Exploration Manager
Title

7-7-81
Date