

KANSAS

A 4x4 grid with a black dot in the second row, second column.

25-15-27W

API# 15-063-20, 165

OPERATOR: OASIS PETROLEUM, INC.

100-2907

1376	ANNY
1907	ANNY
3674	HEED
3696	TOR
3714	LKO
4018	BRN
4123	PAWN
4181	
4237	ORER
4290	ERK MISS
4311	MISS DOE
4313	LTD
4313	LTD

Depth From	To	Formation	Remarks
0	60	Surface soil-post rock	Ran 9 jts of mud 28# 8 5/8"
c 60	925	Shale-sand	Csg. set @ 370' cemented w/
925	1872	Shale-shells	225 sks common 2% Gel 3% CC.
1872	1907	Anhydrite	Centralizer @ 350'
1907	2545	Shale-shells	P.D. @ 3 AM 1/10/1972
2545	3424	Lime-shale	Cement Circ.
3424	3525	Shale-lime	
3525	3728	Lime-shale	
3728	3780	Lime	
3780	3900	Lime-Shale	
3900	4035	Lime	
4035	4054	Lime-Shale	
4054	4315	Lime	
4315	TD		Ran 130 jts of used 15# 5 1/2"

Ran 130 jts of used 15# S 1/2"
csg. set @ 4313' w/150 sks
Salt Sat Pozmix - D.V. Tool
@ 1875' w/400 sks Halcolite
1st @ 1:20 AM, 2nd at 2:30 PM
1/22/1973

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the NE NE SW, Section 25-15S-27W, Gove County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 29th day of January, 1973, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Mammie Lee