

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

18-15-26W

Company- PET. INC.  
Farm- Garvey "L"

No. 2

SEC. 18 T. 15 R. 26W  
APPROX. C SW SE

Total Depth. 4437'

Comm. 10-12-63


Comp. 10-31-63

County Gove  
KANSAS

Shot or Treated.

Contractor. Garvey Drilling Co.

Issued. 3-28-64



CASING:

10 3/4" 303' cem w/225 sx.

7" 4430' cem w/200 sx.

Elevation. 2488' DF

Production. 55 BOPD, 2% WTR.

Figures Indicate Bottom of Formations.

top soil	40
hard sand	105
chalky clay & shale	200
shale blue	307
shale	865
shale & shells	1230
shale & redbed	1285
Blaine Anhydrite	1360
shale, shells, redbed	1770
shale & shells	1950
shale & lime	2035
shale w/lime strks.	2490
shale & lime	2635
lime	2720
lime & shale	2895
shale & lime	3110
lime	3185
shale & lime	3535
lime & shale	3599
lime	3675
chalky shale & lime	3690
lime	4372
lime & chert	4410
lime	4437 RTD
Total Depth	

TOPS: LOG

Anhydrite	1913
Base Anhydrite	1947
Tarkio	3320
Howard	3424
Topeka	3470
Heebner	3708
Toronto	3729
Lansing	3749
Base Kansas City	4042
Pawnee Lime	4184
Ft. Scott	4242
Cherokee Shale	4268
Conglomerate	4313
Mississippi	4330