

36-25-4E

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
 Farm - W. H. Adsit No. 21

SEC. 36 T. 25 R. 4E
 NW SE NW
 990' N & 990' W of Center

Total Depth. 2450' SLM
 Comm. 4-2-49 Comp. 4-26-49
 Shot or Treated. Shot
 Contractor. B. & R. Drlg. Inc.
 Issued. 6-4-49

County. Butler
 KANSAS



CASING:
 8-5/8" 96' Cem. W/ 65 Sx.
 5-1/2" 2420' Cem. W/150 Sx.

Elevation. 1391 Ind

Production. 105 BO, no wtr, 15 hrs.
 after shot (mach.)

Figures Indicate Bottom of Formations.

lime 790
 lime & shale 2425
 lime (dolomite) SLM 2450
 Total Depth

Steel Line Measure:

471 = 471
 596 = 596
 1357 = 1358
 1700 = 1700
 1917 = 1918
 1961 = 1962
 2366 = 2366

Rotary T. D. 2423'

Tops:

Top Lansing 1720
 Base Lansing 1837
 Top Simpson 2420
 Base Simpson 2425
 (Probably erosial Simpson)
 Top Arbuckle 2425

1734-40 very small show oil
 1810-22 very small show oil
 2420-23 good show oil
 2423-25 show of oil
 2425-30 shot oil
 -34 small show oil
 -37 show of oil
 -49 fair show oil

Best pay 2437-2449'
 First free oil 2437'

Fillup 180' oil, no wtr, 6 hrs.

Shot 40 qts. 2429 1/2 - 2450'

Fillup 1950' oil, no wtr, while
 cleaning out. (after shot)