

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

2-32-7E


Company. THE TEXAS CO. ET AL
Farm. D.G. Barger O/A No. 1

SEC. 2 T. 32 R. 7E
SW SW NW

Total Depth. 2252' PB 2219'
Comm. 4-19-55 Comp. 5-2-55

County Cowley
KANSAS

Shot or Treated.
Contractor. Capitt Drlg. Co.
Issued. 6-18-55



CASING:

10 3/4" 123' cem w/100 sx
7" 2252' cem w/150 sx

Elevation. 1114' DF

Production. 40 BO & 75 BW in 5 1/2 hrs.

Figures indicate Bottom of Formations.

surface hole	120
lime & shale	160
lime, red bed & shale	370
lime & shale	465
lime	505
shale & lime	650
lime & shale	915
sandy shale & lime strks.	1150
sandy shale	1240
sand	1310
shale	1415
shale & lime	1615
shale	1670
lime	1675
shale	1757
lime	1765
sandy shale	1800
shale	1854
lime (Lansing)	1904
shale & lime	2130
sand & shale	2168
sand	2 208
lime	2252 RTD
Total Depth	PB 2219'

Tops:	
Topoka	988
Douglas	1568
Stalnaker	1748
Lansing Lime	1856
Kansas City Group	2082
Layton Sand	2092