

18-15-26W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC
Farm- Garvey "L" No. 3

SEC. 18 T. 15 R. 26W
C NE SW

Total Depth. 4400'
Comm. 4-1-64 Comp. 4-19-64
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 8-15-64

County Gove
KANSAS



Elevation. 2478' DF

Production. 75 BOPD 34% Wtr

CASING:

10 3/4" 303' cem w/ 225 sx
4 1/2" 4398' cem w/ 300 sx
2 7/8" 1791' cem w/ 825 sx

Figures Indicate Bottom of Formations.

top soil	40
blue shale. Sand Strks	710
shale & shells	1320
shale	1365
sand, red bed, & shale	1670
red bed & shale	1899
red bed	1902
anhydrite	1940
shale & shells	2340
shale & lime	2545
lime & shale	2660
lime	2735
lime & shale	2790
lime	2885
lime & chalk streaks	3000
lime	3250
lime & shale	3430
shale & lime	3520
lime	3678
lime & chalky streaks	3741
lime	4400 RTD
Total Depth	

TOPS: SCOUT

Queen hill	3568
Heebner	3698
Toronto	3716
Lansing	3737
Base Kansas City	4028
Pawnee	4172
Fort Scott	4230
Cherokee	4258
Mississippi	4321