

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 R. CHENEY
NE SE SE Sec. 20-15S-26W
Gove County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: Ran (8 Jts.) 300' 8 5/8" used 28#,
set @ 306', cemented w/185 sx. common,
plug down @ 7:15 P.M.

COMMENCED: 11/8/75
COMPLETED: 11/21/75

FORMATION	FROM	TO	ELEVATIONS
Sand	0	100	2498 Gr.
Surface Clay	100	801	2500 D.F.
Shale	801	1350	2503 K.B.
Shale & Sand	1350	2048	
Shale	2048	2728	
Lime	2728	4403	
Total Depth	4403		

FORMATION TOPS

Anhydrite	1931 + 572
Base Anhy.	1965 + 538
Heebner	3738 - 1235
Toronto	3757 - 1254
Lansing-K.C.	3777 - 1274
Base K.C.	4075 - 1572
Ft. Scott	4282 - 1779
Reworked Miss.	4364 - 1861
Miss. Dolo.	4395 - 1892
Log T.D.	4401 - 1898

RECEIVED
STATE COMMISSIONER OF GEOLOGY
DEC 1 1975
CONSERVATION DIVISION
WICHITA, KANSAS



STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE SE SE of Section 20-15S-26W, Gove County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 25th day of November, 1975.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard - Notary Public