

KANSAS

Kans. Geo. Survey request
samples on this well.WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 063 — 20,472
County Number

Operator

Rains & Williamson Oil Co., Inc.

Address

435 Page Court Wichita, Kansas 67202

Well No.

#1

Lease Name

Cheney

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Rains & Williamson Oil Co., Inc.

Geologist

Mike D. Engelbrecht

Spud Date

7-7-81

Date Completed

7-17-81


Total Depth

4291'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

State of Kansas
21 T. 15 R. 26 E
SW 1/4 NW
Wichita Branch
County
640 Acres
N

Locate well correctly

Elev.: Gr. 2394

DF KB 2403

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
	12 1/2"	8 5/8"	20#	327'	60/40 poz.	225 sx.	3% cc.
		4 1/2"	10 1/2#	4281'	60/40 poz.	100 sx.	10% salt. 10 bbl. saltwater

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil		
Well No. #1	Lease Name Cheney			
S 21 T 15S R 26 ^{XB} _W				
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME
DST #1 - 3860-3890, 30 (30) 30 (30). Red. 5' mud. FP's 46-46, 38-38. IBHP 62, FBHP 62. DST #2 - 3887-3940, 30 (30) 30 (30). Red. 72' mud. FP's 69-69, 69-69. IBHP 592, FBHP 592. DST #3 - 4248-4291, 30 (30) 60 (45). Rec. 750' GIP, 155' clean oil, 62' VS1.0CM, 62' S1.0CM. FP's 62-100, 131-170. IBHP 1219, FBHP 1219.				E. LOG TOPS
				Heebner 3653 (-1250) Lansing 3694 (-1291) Stark Shale 3959 (-1556) BKC 3983 (-1580) Pawnee 4129 (-1726) Ft. Scott 4189 (-1786) Miss. Dolo. 4280 (-1877) LTD 4293 (-1890)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	 Wilson Rains President 7-21-81			

456969