



Operator Chief Drilling Co., Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #2	Lease Name R. Cheney	Oil Well
S <u>21</u> T <u>15S</u> R <u>26W</u> E W		


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3834-96' 30-30 30-30; Strg. bl. throughout Rec. 180' GIP; 170' MCO IBHP:1250# FBHP:1229# FP: 63-116#			Anhydrite Base Anhy. Heebner Toronto	1845 1880 3646 3668
DST #2 3896-3927' 30-30 30-30; Strg. bl. Rec. 186' GIP; 124' GOCM; 124' M&GCO IBHP: 1281# FBHP: 1270# FP: 42-105#			LKC BKC Pawnee Ft. Scott Miss.	3690 3981 4124 4185 4277
DST #3 3926-60' 30-30 35-35; VWk. Inter. bl. 65", died. Rec. 50' M w/oil spots IBHP: 61# FBHP: 51# FP: 20-20#			LTD RTD	4304 4304
DST #4 3959-90' 30-30 30-30; Wk. bl. 30" Rec. 20' M IBHP: 377# FBHP: 122# FP: 30-40#				
DST #5 4254-94' 30-30 90-60; Wk. bl. Rec. 120' GMCO; 45' GOCM IBHP: 1172# FBHP: 1186# FP: 30-71#				
DST #6 4294-4304' 30-30 90-60 Rec. 60' Gas; 15' Oil; 135' MO IBHP: 1030# FBHP: 1080# FP: 10-51#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Jim Robinson, Vice President
	Title
	November 20, 1978
	Date

196969