


25-15-27W

640 Acres
N

API #15-063-20, 163

Lease Name: Thompson Well No. 1
 Well Located: SE SE NW
SEC 25 TWP 15S RGE 27W
 Operator: Thunderbird Drilling, Inc.
 Address: P. O. Box 18407, Wichita, Kansas 67218
 Elevation: Ground D.F. K.B. 2437'
 Type Well: (Oil, gas, dry hole) Oil

Drilling Commenced: 11/26 1972 Drilling Completed: 12/7 1972
 Well Completed: 1/23 1972 Total Depth RTD 4320'
 Initial Production: 1/23/73 Pumped 99 BO, no water in 24 hours. *h*

Casing Record

Size: 8 5/8" Set at 310' Size: Set at
 Size: Set at Size: Set at

Liner Record

Size: Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>5 1/2"</u>	<u>w/100 sx</u>	<u>common</u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>

Perforations

Formation	Perforated Interval and Number Shots
<u>No perfs.</u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

Electric Log Run (Show type log and depths covered)

Radiation Guard Log

(Fill in formation and related information on reverse side)

Lansing	3712'	-1275
BKC	4017	-1580
Marm.	4059'	-622
Pawnee	4149'	-1712
Ft. S.	4208'	-1771
Cher.	4234'	-1797
Miss.	4310'	-1873
RTD	4320'	-1883

DST #1, 3954-80', open 60", rec. 10'
BHP's 908-778#/30", FP 61-61#.

DST #2, 4046'-4145', open 60", rec. 15' m
BHP's 95-95#/30", FP 69-87#.

DST #3, 4270-4320', open 90", rec. 240' very
heavily oil and gas cut mud and 760' gassy oil,
BHP's 1159-1081#/45", FP 78-294#.

25-15-27w

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
SURFACE SAND	0	310
SAND & SHALE	310	1189
SHALE & SHELL	1189	1873
#2 ANHYDRITE	1873	1909
SHALE	1909	1941
SHALE & LIME	1941	2630
LIME	2630	2722
LIME & SHALE	2722	3037
LIME	3037	4320
TOTAL DEPTH	4320	

LOG TOPS:

Anhy.	1872
Heeb.	3672
Toronto	3692
Lansing	3710
BKC	4016
Marm	4064
Paw.	4150
Ft. S.	4210
Cher.	4235
Miss	4310
LTD	4320

