

CASING RECORD:
340.63' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.

DESCRIPTION: NW SW NW
Section 26-15S-27W
Gove County, Kansas

TOTAL DEPTH:
4342'

COMMENCED: June 3, 1973

COMPLETED: June 16, 1973

Elev. 2474 kb

FORMATION

FROM

TO

REMARKS

Shale, Clay & Sand	0	360
Sand	360	1180
Shale	1180	1480
Sand	1480	1700
Shale	1700	1855
Shale w/Sand Streaks	1855	2222
Lime & Shale	2222	3330
Lime	3330	3474
Lime & Shale	3474	3859
Lime	3859	3915
Lime & Shale	3915	4047
Lime	4047	4133
Lime & Shale	4133	4180
Lime	4180	4243
Lime & Shale	4243	4320
Lime	4320	4342

Ran 340.63' of used 8-5/8" surface casing; set and cemented at 346.63' with 225 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:25 P. M. June 4, 1973.

Ran electric log.

Rotary Total Depth: 4342'

Log tops

anhy	1919
heeb	3696
tor	3717
lkc	3736
bkc	4036
mrn	4090
pawn	3169
ft sc	4223
cher	4250
miss	4314
rtd	4342
ltd	4343

5 1/2" casing set and cemented at 4334' with 100 sacks of common cement. Collar set at 1924' with 375 sacks of common cement, 12% gel and 5% salt. Plug down at 1:30 P. M. June 16, 1973.

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Stearns
Charles W. Stearns, President

