

State Kansas County Lawrence


Company Messman-Linehart Well No. 1

Farm Malone-Dwyer

Survey C SW 1/4 SW 1/4

Block No. 5 Sec. 5 Twp. 21S Range 16W

Co-Ord. 505 Elev. 1000



Washedown of Rupp,
Woodman-Sarnitti
#1 Malone & Dwyer
DHM #2,000.00
Sarnitti Oil Company
2 1/2 m.
C.B.R.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
1972		M1 today & set up
Dec 13		Digging cellar
Dec 14		Drilled rock hole
		4:45 p.m. 6:15
		drilled cement
		plugged. 30' cement
		in pipe washed
Dec 15	1975	down 1975'
		On bank with lick
Dec 16	3970	clean out hole

697213

Date	Depth	
Dec 17		DST #1 3789-3803
		Og 30" Shut in 45"
		Og 1 hr Shut in 1 hr
		Strong blow diminishing
		to good blow free
		1350' surface water
		IR 170-583 RBHP
		1596 #/45" RF 575-
		596 RBHP 606 #/1 hr
		Temp 126°
Dec 18		DST #2 3787-3830
		Og 10" Shut in 30"
		Og 45" Shut in 45"
		Strong blow diminishing
		to good blow free
		1550' water very slight
		gas cut. IR 363-502
		RBHP 972 #/30" RF
		596-690 RBHP
		805 #/45" Temp 123°
		plugged hole
		plugging completed
		2:30 a.m. Dec.
		18th.