

Date	Depth	697229
10-21	D.S.T. #1	4110-60 open 2 hrs.
		Wk. initial blow - inc slowly
		Rec. 660' gas in pipe &
		20' mud. IBHP 172#;
		IF 47#; Temp. 120°
		FBHP 267; FF 54
	3593	Heebner
	3710	Brown Lime
	3717	Lansing (-1641)
	4114	Base Ft. Scott
10-22	4118	Congl. (-2042)
	4230	Viola Chert (2154)
R.T.D	4250	
	D.S.T. #2	4160-4250 open 1 ^{hr.} 20"
	No Sand, Sec.	Size 60"
		weak to fair blow
		Rec 1020' gas in drl. Pipe
		Plus 70' mud with a
		Scum of oil
		IBHP 196 FBHP 315 #
		IFP 39# FFP 62 #
		Temp 120°
	No. Log.	D & A