

S.E. St. John Prospect

State Kansas County Stafford

Company Messman-Ruehnt Air Co. Well No. 1

Farm Spare "B" (wash down)

Survey General Del. Co. #1 (Asher)
(Ord. - 1953)

Block No. 10 Sec. 10 Twp. 24 Range 13

Co-Ord. 1911 R/B

new wire Center - Garvey Del.

			0		

34% - a. a. Seeligson, Jr.

16% - Rayona Shuler
Seeligson

50% - Messman-Ruehnt
Air Co.

85 1/8" @ 440'

4050 w.o. to be conn.

by 4-10-67

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4-1-67		M.I.R.I.
4-3		D.S.G. #1-3786-67 (straddle) ap 1 hr - 40" fr. bl. dev. three test, Rec. 100' mud w/ few spts oil, H.P. 370-170 #, F.P. - 52-68 # Temp. 110°

Date

Depth

697323

4-4 - D.S.J. #2 - 3752-67 (straddle)
 of 1 hr 30", med. bl. to
 Rec. 60' gas, 44' Ocm
 1' fr. oil, IAP - 1151-
 IAP - 26 - 37P - 30"

3 IAP (45") 642# (steel
 bldg. sharply), Temp. 109°

D.S.J. #3 3550-3622 (straddle)
 fair blow throughout
 Rec. 1500 gas, 130 hrs

O+ Ocm 60' oil O+ Ocm
 60' oil O+ Ocm with BIP

1202-1161[#], 3P 52-116[#]

5 1/2" @ 3830' w/125 ex.

cem, 2 gal, 13 salt

P.D.C 5:30 P.M. 4/5/67

D.S.J. #4 (straddle) - 3695-3710

of 1 hr., wh. bl. dead
 in 5", Rec. 10' med.

IAP - 1306-923[#]

3 I. 10-10[#], Temp. 112°

4-7-67

M.S.C.J., c.o. to 3800'

Ray Gamma Callahan

Date

Depth

697323

Set plug + prep. 3590 - 94'
w/ 4^{1/2} ft., 1000 gal. acid
Sub. back load, let set
overnight

4-9 16 bf. Jellip (40% oil)
30" v. - swb. 5.8 bf. (40% oil)
next hr. - swb. 5.2 bf. (30% oil)
Sub. rest of day + fluid
degr. to 1 bbl./hr. (25% oil)
Preparing to pull pipe
+ abandon

4-19 Pulling Pipe