

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location C NE SE.

Sec. 32 T. 32 R. 5E.

660' fr NL 660' fr EL SE/4

Casing Record

County- Cowley.

20" 10" Farm- E. P. Graves No. 1

15 $\frac{1}{2}$ " 8 $\frac{1}{2}$ " 379'. Company- Roth & Faurot.12 $\frac{1}{2}$ " 6 $\frac{5}{8}$ " 625'.

Contr.-

53/16"

Comm.- 8/27/1928.

Comp.-

9/10/28.

Total Depth 659'

Shot

Quarts Between

Correspondence Regarding This Well Should Be Referred to


Elevation

Figures Indicate Bottom of Formations.

Initial Production

Date Issued. 3/16/1929.

200,000' Gas.



Formation	Depth
lime	25
blue slate	40
white shale	70
lime	80
shale	90
red rocks	100
blue shale	110
lime	115
blue slate	120
lime	130
red rock	135
white slate	140
lime	178
1/2 BW 145-150'	
shale	183
red rock	200
lime	210
shale	235
lime	240
shale	255
red rock	265
white shale	300
lime	310
white shale	315
brown shale	342
lime	344
red rock	365
blue shale	375
Set 8 $\frac{1}{2}$ " at 370'	
lime	380
white slate	410
lime	415
white shale	425
red rock	431
lime shell	435
shale	438
lime	490
shale white	500
brkn lime	540
gray shale	618
Set 6 5/8" 615'	
gas sand	629
shale	640
lime	644
shale	659
Total Depth	659'.