

State Geological Survey  
WICHITA, BRANCH

15-063-20223

3-15-28W

RECEIVED  
STATE CORPORATE COMMISSION  
WELL LOG

AUG 26 1974

CONSERVATION DIVISION  
Wichita, Kansas

CHIEF DRILLING CO., INC. &  
BILL J. PORTER  
Suite 905 Century Plaza  
Wichita, Kansas 67202

#1 J.M. COBERLY  
C NE SW Sec. 3-15-28W  
Gove County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.  
CASING RECORD: Set 244.66' 8 5/8" w/180 sacks  
cement; 4369' 4 1/2" w/250 sacks salt  
sat. 60-40 posmix & 500 sacks 50-50  
posmix 6% gel.

COMMENCED: 7/27/74  
COMPLETED: 8/20/74

FORMATION	FROM	TO	ELEVATION
Surface Clay & Sand	0	253	2540 Gr.
Shale & Sand	253	1750	2542 D.F.
Shale	1750	1832	2545 K.B.
Anhydrite	1832	1869	
Shale	1869	1948	
Shale & Shells	1948	2325	
Shale	2325	2600	
Shale & Lime	2600	2764	
Shale & Shells	2764	2960	
Shale	2960	3126	
Lime & Shale	3126	3576	
Shale & Lime	3576	3890	
Lime & Shale	3890	3915	
Lime	3915	3925	
Lime & Shale	3925	3945	
Lime	3945	4140	
Hard Lime	4140	4141	
Lime	4141	4365	
Total Depth	4365		

ELECTRIC LOG TOPS

Anhydrite	1957 +	588
Base Anhy.	1992 +	553
Heebner	3661 -	1116
Toronto	3682 -	1137
Lansing	3700 -	1155
Stark	3953 -	1408
B.K.C.	4016 -	1471
Altamont	4079 -	1534
Pawnee	4113 -	1568
Ft. Scott	4205 -	1660
Cherokee	4231 -	1686
Conglomerate	4286 -	1741
Miss. Dolomite	4339 -	1794
L.T.D.	4367 -	1822

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE SW of Section 3-15-28W, Gove County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Jim Robinson*  
Jim Robinson, Vice President

sworn to before me this 23rd day of August, 1974.

*Virginia S. Fabian*  
Virginia S. Fabian, Notary Public

