

IMPORTANT
Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 063 — 20,294
County Number

Operator

Olympic Petroleum Company

Address

2121 South Columbia Ave. Tulsa, Oklahoma 74114

Well No.

#1

Lease Name

R. S. Coberly "A"

Footage Location

100' SE of center SW $\frac{1}{4}$ SE $\frac{1}{4}$ Section 4
feet from (N) (S) line feet from (E) (W) line

Principal Contractor

Dunne-Gardner Petroleum

Geologist

Marvin Frankamp

Spud Date

April 4, 1976

Total Depth

4345'

P.B.T.D.

none

Date Completed

April 21, 1976

Oil Purchaser


none

S. 4 T. 15 R. 28 W

Loc. C SW SE

County Gove

640 Acres
N



Locate well correctly

Elev.: Gr. 2544

DF 2554 KB 2553

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing		8 5/8		330	regular	250	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
none		

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
none		

TUBING RECORD

Size	Setting depth	Packer set at
none		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
none					
RATE OF PRODUCTION PER 24 HOURS	Oil none	Gas none	Water none	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator OLYMPIC PETROLEUM COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name R. S. COBERLY "A"	DRY HOLE	
S 4 T 15S R 28E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH
			WELEX RADIATION-GUARD LOG
Blue shale	0	330	
Shale & shells	330	1865	Anhydrite 1967 (+586)
Red bed	1865	1972	Base Anhydrite 2007 (+549)
Anhydrite	1972	2007	Heebner 3662 (-1109)
Shale & shells	2007	2440	Lansing 3702 (-1149)
Shale	2440	2650	Stark Shale 3944 (-1391)
Shale & lime	2650	3720	Base Kansas Cty 4008 (-1455)
Lime	3720	4317	Marmaton 4032 (-1479)
Shale & lime	4317	4345	Altamont 4074 (-1521)
Rotary Total Depth	4345		Pawnee 4120 (-1567)
			Upper. Cherokee 4190 (-1637)
			Ft. Scott 4215 (-1662)
			Lwr. Cherokee 4224 (-1671)
			Mississippian 4308 (-1755)
			Elec. Log TD 4345 (-1792)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	OLYMPIC PETROLEUM COMPANY By: <u>James E. Silver</u> James E. Silver Signature Managing Partner Title May 3, 1976 Date		