



Operator Name DaMar Resources, Inc. & McDonald-Wallace Petroleum Co., Inc. Lease Name Roberts Ladd Well # 1

Sec. 10 Twp. 15s Rge. 28  East  West County Gove

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No

DST #1 - 3795 - 3870 (H, I)  
 30-60-15-15  
 ISIP - 1152  
 FSIP - 617  
 IFP - 61-61  
 FFP - 92-92  
 Recovery: 1' FO and 60' OCWM

DST #2 - 4104 - 4190 (Myrick Stat, Fort Scott)  
 30-60-45-60  
 ISIP - 1101  
 FSIP - 1070  
 IFP - 154-185  
 FFP - 236-277  
 Recovery: 1' CO and 545' MW

Name	Formation Description	
	Top	Bottom
Heebner	3605	(-1120)
Lansing-K.C.	3642	(-1157)
Stark Shale	3897	(-1412)
Base Lansing-K.C.	3963	(-1478)
Pawnee	4084	(-1599)
Myrick Station	4122	(-1637)
Fort Scott	4159	(-1674)
Cherokee Shale	4184	(-1699)
Mississippi	4257	(-1772)
R.T.D.	4300	(-1815)
L.T.D.	4299	(-1814)

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	20#	329	50/50	180	2% gel 3% CC
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
Shots Per Foot	Specify Footage of Each Interval Perforated			(Amount and Kind of Material Used)		Depth	
TUBING RECORD				Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No			
Date of First Production		Producing Method					
		<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (explain).....					