

10-15-28W

WILLIAMSON DRILLING, INC.

5501 NAVAJO

GREAT BEND, KANSAS 67530

(316) 793-8229

DRILLERS' WELL LOG

Date Commenced: 9-8-86
Date Completed: 9-16-86

DaMar Resources
Roberts/Ladd #1
S/2 SW/4 NW/4
Section 10-15s-28w
Gove County, Kansas

Elevation: 2480 G.L.
2485 K.B.

Surface Pipe: Ran 8 joints of 8 5/8" CSG 20#. Cemented with 180 sks.
50/50 poz, 2% gel, 3% cc. Cement did circulate. Pipe was new.

0-1380' Surface Soil, Clay, Sand, Shales
1380-1480' Sand
1480-1720' Shale & Lime
1720-1907' Redbed
1907-1945' Anhydrite
1945-2300' Redbed, Shales
2300-2380' Salt
2380-3340' Shale w/Lime Stringers
3340-3400' Shale
3400-3678' Lime w/Shale Stringers
3678-3682' Carb. Shale
3682-4180' Lime w/Shale Stringers
4180-4190' Carb. Shale
4190-4208' Lime
4208-4220' Carb. Shale
4220-4244' Lime & Shaley Lime
4244-4250' Carb. Shale
4250-4280' Shales w/Lime Stringers
4280-4300' Dolomite
4300' R.T.D.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss.

Terry L. Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his