

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOG

15-063-20366


API No. 15 — 063 — 20,366
County Number

S. 14 T. 15 R. 28 E
W

Loc. W2 E2 NE

County Gove

640 Acres
N



Locate well correctly

Elev.: Gr. 2469

DF 2471 KB 2474

Operator

T & D Oil Co.

Address

P. O. Box 301 Victoria, Kansas 67671

Well No.

#2

Lease Name

Bentley

Footage Location

1320 feet from (S) line

400 feet from (W) line

Principal Contractor

DNB

Geologist

Francis Whisler

Spud Date

12-7-77

Total Depth

4300

P.B.T.D.

3938

Date Completed

12-21-77

Oil Purchaser

Permian

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	223	Common	160	
Production	7 7/8	4 1/2	9 1/2	3900	Common	175	10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	D.P.'s Jet	3884-88
			4	D.P.'s Jet	3642-46

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8	3934	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 1-5-78		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 40	Gas bbls.	Water MCF	Gas-oil ratio None	CFPB bbls.
Disposition of gas (vented, used on lease or sold) Vented			Producing interval (s) 3642-46		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator <u>T & D Oil Company</u>		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: <u>oil</u>
Well No. <u>2</u>	Lease Name <u>Bentley</u>	
S <u>14</u> T <u>15</u> R <u>28</u> W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite <u>Log Tops:</u>	1908			
Heebner	3604			
Toronto	3623			
Lansing	3640			
BKC	3961			
Marmaton	3988			
Pawnee	4115			
Fort Scott	4150			
Cherokee Shale	4174			
Mississippi	4252			
DST #1 Tool open 5, closed 60, open 30, closed 60 Recovery; 1565 G ip 1475 CRan Gassy Oil	3637	3670		
I.F.P. 123-153 I.B.H.P. 1065 F.F.P. 161-459 FBHP 1059				
Completion; Perf. 3884-38, Tested 4 BBL wtr Per Hour. Set Bridge Plug @ 3860. Perf. 3642-46. Hole Filled up with 2800 of oil No water. Put on Pump				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<u>Thomas D. Younger</u> Signature <u>Operator</u> Title <u>1-14-78</u> Date
---------------	---