

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NE c SW


Sec. 18 T. 32 R. 6E

300' S of NL & 300' W of EL SW/4

Casing Record

County Cowley

20" 10" 1615 Farm- Cook No. 1
 15 1/2" 8 1/4" 1982 Company- Lewis Production Co. & Pryor & Lockhart
 12 1/2" 450 65/8" 2460 Contr.- Arthur Brewer & Co.
 12 1/2" 1155 53/16" 3036 Comm.- 4/16/1928. Comp.- 5/24/1928.
 Total Depth 3062' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation Initial Production Dry.

Date Issued. 6/23/28.

Formation	Depth	Formation	Depth	Formation	Depth
lime	15	lime	910	blue slate	2025
clay	20	shale	920	lime	2090
lime	40	lime	925	blue slate	2227
shale	50	shale	950	lime	2229
lime	90	lime	955	black slate	2245
red rock	100	shale	1000	lime	2267
shale	130	lime	1030	brkn sand	2317
lime	140	shale	1045	4 BW 2295'	
shale	145	lime	1065	water sand	2395
red rock	150	shale	1155	HFW 2345'	
lime	170	lime 3 BW 1160'	1185	blue shale	2447
shale	180	shale	1200	lime	2485
lime	200	lime	1205	black slate	2495
shale	205	shale	1210	lime	2555
red rock	215	lime	1245	blue shale	2645
lime	220	shale	1250	lime	2655
shale	230	lime	1270	1/2 BW 2655'	
lime	260	shale	1280	drk shale	2665
shale	270	lime	1290	lime	2670
red rock	275	shale	1295	blue shale	2720
lime	285	lime	1305	lime	2745
shale	295	shale	1310	black slate	2751
lime	300	lime	1330	lime	2770
shale	310	shale	1340	black slate	2775
lime	320	lime HFW 1365'	1355	lime	2779
red rock	350	water sand	1390	white slate	2820
lime	355	shale	1400	lime	2825
red rock	370	water sand	1420	drk shale	2960
lime	400	shale	1430	brkn lime	2970
shale	405	water sand	1445	drk shale	2982
lime	417	shale	1455	black shale	3030
red rock	422	sand	1483	chat	3036
lime	427	shale	1490	lime	3041
shale HFW	430	sandy lime	1495	sand	3053
sand	450	shale	1510	Show oil 3041'	
shale	455	lime	1515	lime	3062
lime	460	shale	1555		
shale	465	lime	1560	Total Depth	3062'
lime	490	shale	1575		
shale	495	red rock	1580		
lime	510	lime	1585		
shale	515	shale	1595		
lime	525	red rock	1605		
shale	565	shale	1620		
lime	570	lime	1630		
shale	575	shale	1635		
lime	580	lime	1660		
shale	605	red rock	1665		
lime	620	shale 1/2 BW 1685'	1680		
shale	640	sand	1695		
lime	660	lime	1705		
shale	740	shale	1835		
lime	745	lime	1843		
shale	815	blue slate	1888		
lime	820	gray sand	1920		
shale	825	HFW 1925			
lime 1 BW 855'	860	water sand	1960		
shale	865	blue slate	1963		
lime	880	lime	1966		
shale	890	sand	1975		