

Company SHELL OIL, INC.
Farm L. A. Mattock No 1

SEC. 26 T. 25 R 6E
NE NW SW
330' fr N1 & 1007' fr WL SW 1/4

Total Depth. 2745'
Comm. 4-1-48 Comp. 4-28-48
Shor or Treated.
Contractor
ssucc 9-18-48

County. Butler
KANSAS



CASING
8-5/8" 69' Con. W/40 Sx.

Elevation. 1344 3rd

Production. Dry

Figures indicate Bottom of Formations.

shale & lime	67
shale	72
lime & shale	1409
lime buff	1430
shale	1472
lime	1485
shale sdy	1505
lime shaley	1512
sand por. NSO	1521
lime	1526
sand	1530
shale sdy	1550
sand	1568
shale sdy	1595
lime buff & tan	1598
shale	1675
lime shaley	1688
shale	1760
lime por. NSO	1912
shale	2050
lime no show	2083
lime cherty	2220
shale	2355
lime slyn	2365
shale	2412
lime & shale	2473
shale slightly sandy	2518
shale very sdy	2532
shale sdy, thin strks lime	2713
sand no show	2717
shale & lime	2723
sand no show	2727
shale	2730
chert	2734
dolo. cherty	2740
lime chalky	2745
Total Depth	

Tops Schlumberger:

Lansing	1760
Kansas City	2055
Bart. Sand @	2713
no shows	
Mississippi	2730