

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


5-15-29W

Company- WYCOFF BROTHERS
Farm- J. H. Lungren No. 1

SEC. 5 T. 15 R. 29W
C NW SW

Total Depth. 4310'
Comm. 10-25-61 Comp. 11-3-61
Shot or Treated.
Contractor. A. L. Jackson
Issued. 1-27-62

County Gove KANSAS



CASING:
8" 103'
5" 4309'

Elevation. 2572' KB

Production. 45 BOPD

Figures Indicate Bottom of Formations.

surface clay	70
blue shale	108
shale	930
shale, shells & red bed	1415
shale, red bed	1962
Anhydrite	1995
shale	2155
shale, shells & red bed	2330
shale	2576
shale & lime	2660
shale	2720
lime & shale	3505
lime	3588
lime & shale	3630
lime	4243
lime - Mississippi	4270
lime	4310
Total Depth	

TOPS: SCOUT	
Anhydrite	1967
Base Anhydrite	1997
Heebner	3586
Toronto	3604
Lansing	3620
Stark Sh.	3860
Hushpuckney Shale	3896
Pawnee	4051
Ft. Scott	4115
Cherokee Shale	4140
Mississippi Lime	4205
Mississippi Dolomite	4208