

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

4-15-29W


Company- AURORA GASOLINE CO. & MURFIN DRIG. CO.  
Farm- Lundgren No. 1

SEC. 4 T. 15 R. 29W  
NE NE NW

Total Depth. 4369'  
Comm. 2-6-59 Comp. 2-22-59  
Shot or Treated.  
Contractor. Murfin Drig. Co.  
Issued. 4-25-59

County Gove

KANSAS



Elevation. 2540' DF

CASING:

8 5/8" 231' cem w/160 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	231
shale	350
shale-shells	910
shale-sand	1000
shale-shells	1130
sand	1200
hard sand-shale	1300
red bed - shale	1405
Anhydrite	1438
red bed	1740
red bed & shale	1955
Anhydrite	1985
shale - shells	2300
lime & shale	3604
lime	3645
lime - shale	3695
lime	4369
Total Depth	

TOPS: DRILLERS

Anhydrite	1405
Base Anhydrite	1955

LOG TOPS:

Heebner	3587
Toronto	3607
Lansing	3623
Base Kansas City	3943
Marmaton Lime	3961
Conglomerate	4206
Mississippi	4218

DST #1 3869-98', op 1 hr, rec. 120' slightly oil & gas cut mud, 90' oil & gas cut mud, 180' oil & gas cut muddy water, 180' salty water, IF 70#, FF 245#, IBHP 1140#/20 min. FBHP 752#/20 mins.

DST #2 4181-4205', op 1 hr, rec. 80' mud, IF 23#, FF 52#, IBHP 0#, FBHP 60#/20 mins.