


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

Company - SKELLY OIL COMPANY  
Farm - R.H. Hazlott No. 45

SEC. 19 T. 25 R. 5E  
NW SE SE  
990' fE1 & 940' fS1 SE  $\frac{1}{4}$

Total Depth. 2478'  
Comm. 3-24-47 Comp. 4-6-47  
Not or Treated.  
Contractor. Morrison Drilling Co., Inc.  
Issued. 10-14-47

County. Butler  
KANSAS



O.D. CASING:  
10-3/4" 150' Cem. w/150 sx  
7" 2475' Cem. w/250 sx

Elevation. 1388 feet

Production. 65 BO & 20 BW

Figures Indicate Bottom of Formations.

lime & shale	0-40
lime hrd	128
lime & shale	160
lime & shale	465
shale & shells	820
lime & shale	900
shale & shells	1000
lime	1050
lime & shale	1135
lime w/shale brks	1290
lime & shale	1350
shale & shells	1430
lime & shale	1545
lime w/shale brks	1575
lime	1635
lime & shale	1660
lime w/few shale brks	1750
lime hrd	1765
shale w/lime brks	1845
lime hrd w/shale brks	1890
shale	1927
lime & shale	2011
shale & shells	2060
lime	2071
shale	2084
lime brkn	2170
shale sdy	2226
shale w/lime brks	2285
limo & shale	2474
lime	2476
lime	2478 SLM
Total Depth	

Top of Viola Lime 2474

Producing Formation:  
Viola Lime 2475-2478

Fair porosity & saturation  
2474-76