

LOG OF WESTERFIELD #1 TEST

Casing Record:
 15 1/2" set at 47'
 12 1/2" " " 657'
 10" " " 1150'
 8 1/2" " " 1780'
 6.5/8" " 2360'
 5" " "

Location: SW corner of NW 1/4
 NE 1/4 of Sec. 1,
 T 32, R 8E in
 Chautauqua County
 Kansas

Drilled By
 THE SYNDICATE OIL & GAS CO.
 139 N. Mead Ave.
 Wichita, Kansas.

<u>Formation</u>	<u>Total Depth</u>	<u>Remarks</u>	<u>Formation</u>	<u>Total Depth</u>	<u>Remarks</u>
Soil	5		Lime	2625	
Chat	15		Shale	2685	
Slate	25	3 B.W. at 25'	Wilcox Sand	2700	H.F. Water 2695'
Lime	30				
Slate	225				
Lime	240				
Slate	370				
Lime	390				
Slate	410				
Lime	440				
Slate	480				
Red Rock	490				
Slate & Shells	525				
Lime	535				
Slate & shells	595				
Shale	620				
Water sand	655	Hole Full Water 625'			
Slate	700				
Lime	735				
Shale	740				
Sand	770	H.F. Water 745'			
Red Rock	775				
Slate	810				
Red Rock	825				
Slate	875				
Sandy Lime	970	Water 885'			
Shale	1020	6 B.W. 1005'			
Slate	1070				
Lime	1085				
Shale	1100				
Water Sand	1115	H. Full Water 1110'			
Sand	1147				
Slate	1240				
Lime	1270				
Broken Lime	1300				
Slate	1370				
Shale	1400				
Slate	1410				
Broken Lime	1495				
Sand	1560				
Lime	1660				
Sand	1705	H.F. Water 1670'			
Lime	1765				
Black Slate	1775				
Lime	1780				
Slate	1790				
Lime	1825				
Slate & Shells	1855				
Slate	1900				
Lime, Sandy	1965	1 B.W. 1930'			
Slate	1975				
Lime	2010				
Slate	2015				
Lime	2055				
Shale	2245	2 B.W. 2245'			
Sandy Shale	2275				
Slate	2285				
Red Rock	2290				
Shale	2330				
Sand	2345				
Lime	2360				
Lime, very hard	2390				
Sandy Lime	2450	H. Full W. 2415'			