

State Geological Survey
WICHITA, BRANCH

D R I L L E R S L O G

15-063-20284
6-15-29W

#1 Lundgren

CASING RECORD:
313.32' of used 8-5/8"
surface casing.

COMPANY: Okmar Oil Company

DESCRIPTION: E/2 SW NE
Section 6-15S-29W
Gove County, Kansas

CONTRACTOR: Strata Drilling Company

TOTAL DEPTH:
4295'

COMMENCED: December 29, 1975

COMPLETED: January 12, 1976

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock & Shale	0	325	Ran 313.32' of used 8-5/8" surface casing; set and cemented at 318.82' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 1:30 A. M. December 30, 1975.
Shale & Sand	325	1970	
Shale	1970	2295	
Shale & Lime	2295	3395	
Lime	3395	3590	
Lime & Shale	3590	3732	
Lime	3732	3885	
Lime & Shale	3885	4232	
Lime	4232	4295	

ROTARY TOTAL DEPTH: 4295'

Ran Drill Stem Tests.

Ran Electric Log.

Ran 136 joints of used 5 1/2" casing; set and cemented at 4294' with 200 sacks of common cement and 18% salt. First stage plug down at 3:45 A. M. D. V. tool set at 1967' with 500 sacks of light cement. Plug down at 7:00 A. M. January 12, 1976.

RECEIVED
STATE GEOLOGICAL COMMISSION

FEB 4 1976

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.