

State Geological Survey  
WICHITA, BRANCH

6-15-29S

CONTRACTOR'S WELL LOG

15-063-20305

OPERATOR: OKMAR Oil Company  
CONTRACTOR: Abercrombie Drilling, Inc.  
WELL NAME: LUNDGREN #2  
LOCATION: N/2 S/2 NE/4, Section 6-15S-29W  
Gove County, Kansas  
SPUD DATE: July 29, 1976  
COMPLETION DATE: August 11, 1976

0	300	Sand
300	345	Shale
345	1564	Shale & Sand
1564	3003	Shale
3003	3410	Shale & Lime
3410	4326	Lime
	4326	Rotary Total Depth

Drilled 345' of 12 $\frac{1}{2}$ " hole, set 332.73' of used 8 5/8" casing, set at 340.73', cemented with 180 sx. 60/40 posmix, with 2% gel, 3% Ca. Cl, followed by 25 sx. of common cement, 2% gel, 3% Ca. Cl. Cement did circulate. Plug down at 8:00 a.m. - 7-29-76

Set pipe at 4329', Cemented with 200 sx. common cement, 18% salt, Cemented by Halliburton. Plug down at 4:15 p.m. on August 11, 1976

SAMPLE TOPS:


Anhydrite 2010'  
B/Anhydrite 2040'

STATE OF KANSAS )  
) SS  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the LUNDGREN #2 N/2 S/2 NE/4, Section 6-15S-29W, Gove County, Kansas.

ABERCROMBIE DRILLING, INC.

By:



Jack L. Partridge, Asst. Sec. Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 17th day of August, 1976.