


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Chosney No. 139

SEC. 21 T. 25 R. 5E
NW NE SE
320' S & 990' W of E $\frac{1}{2}$ corner

Total Depth. 2430'
Comm. 7-28-47 Comp. 8-29-47
Shot or Treated.
Contractor. B & R Drilling Co.
Issued. 11-14-47

County. Butler
KANSAS



CASING:
5 $\frac{1}{2}$ " 2356' Com. w/200 sx

Elevation. 1369 Act. 414

Production. 102 BO & no wtr in
24 hours.

Figures Indicate Bottom of Formations.

limo	0-45
lime & shale	288
shale sdy & limo	480
shale & limo	1390
shale sdy & limo	1450
coreing	1486
shale	1542
lime & shale	1620
limo	1749
lime brkn & shale	1809
lime & shale	1937
limo	2063
lime & shale	2157
coreing	2193
lime & shale	2263
limo	2306
shale & limo	2359
limo	2376
limo & chert	2413
limo	2430
Total Depth	

Steel Line Measure:

1052-1052
1907-1907.38
2123-2120.37

Tops:

Douglas Sand	1448
Iatan Ls.	1535
Good Show Oil	1435-45
Base Iatan Ls.	1558
Lansing Limo	1621
Poor Show Oil	1626-31
Good Show Oil	1662-73
Fair Show Oil	1673-84
Base Lansing L ^{ime}	1734
Kansas City	1910
Fair Show Oil	1916-44
Fair Show Oil	1960-72
Base Kansas City	2080
Marmaton Sand	2150
Good Show Oil	2150-88
Base Marmaton Sand	2188
Arbuckle Ls.	2355
First Pay	2384-87
Best Pay	2378-87
	2395-2400
	2417-2430