


State Kansas County Ellis
Company G-M-R Oil Co. & Newmont Well No. 2
Farm Wolf "A":
Survey
Block No. Sec. 4 Twp. 13S Range 17W

Co-Ord. C.P. 3225-50 Elev. 2061 KB
NE SE SW 2056 GL



Rig #3

3/4-Newmont Oil Co.

1/4-GMR Oil Co.

Catherine, N.W. Pool Geol: V. Hess

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 990 Ft. from S. Line

2310 Ft. from W. Line Ft. from E. Line

Date	Depth	
		SPD 5-10-55
5-10		MIRT
5-11		8 5/8" @ 202' w/125 sx cem, 2% gel, 3 cc. PD 10 p.m. 5-10 WOC
5-12	1246	Anhydrite (+815)
5-13	2355	Drlg
5-14	2908	Drlg ($\frac{1}{2}^{\circ}$ off 2900)
5-15	3025	Topeka (-964)
	3273	Heebner (-1212)
	3218	Drlg

Date	Depth	700753
5-16	3294	Toronto (-1233)
	3342	Lansing (-1281)
		DST #1 3337-65', op 1 hr, cl 20". Fair bl throughout. Rec 390' mdy wtr w/scum oil. BHP-990#
	3365	Drlg
5-17	3408-21'	DST #2 3408-21', op 20", cl 10". Rec 90' hv ocm & 90' gas in pipe. BHP-340
	3464	Drlg
5-18	3578	Conglomerate (-1517) (No Arbuckle)
	3633	R.T.D. Ran Halliburton Log
5-19		5½" @ 3555' w/60 sx Posmix. P.D. 6:40 p.m. 5-18-55.
6-4		MICT
6-6		DOC to 3523. Perf 3408-12/13 ^s 1 qt. fluid (50% wtr & 50% mud)
		Acidized w/500 gals. 300' fill up. Started swb 10 BFPH, 6% wtr; completed @ 10 BFPH, 2% wtr. Putting on pump.
6-15-56		Making 3½ BWPD