

WICHITA BRANCH
KANSAS DRILLERS LOG

S. 17 T. 15 R. 29 K
W

Loc. C NW NE

County Gove

API No. 15 — 063 — 20,314
County Number

Operator
Dunne-Gardner & Sotexco, Inc.

Address
Suite 250, 200 West Douglas, Wichita, Kansas 67202


Well No. 1 Lease Name Fletcher

Footage Location
660 feet from (N) (X) line 660 feet from (W) line

Principal Contractor Dunne-Gardner Petroleum, Inc. Geologist George A. McCaleb

Spud Date November 17, 1976 Total Depth 4290 P.B.T.D.

Date Completed November 24, 1976 Oil Purchaser



Elev.: Gr. 2540

DF KB 2549

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	318'	Common	250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Dunne-Gardner Petroleum, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry hole

Well No. 1 Lease Name Fletcher

S 17 T 15 R 29 W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay, shale and sand	0	320	Heebner	3598
Shale and shells	320	1350	Toronto	3620
Shale	1350	1560	Lansing	3639
Sand	1560	1715	B/KC	3960
Shale and shells	1715	1957	Marmaton	3969
Anhydrite	1957	1987	Pawnee	4050
Shale and shells	1987	2270	Ft. Scott	4120
Shale and lime	2270	3700	Cherokee	4133
Lime	3700	4290	Mississippi	
			Lime	4244
			Mississippi	
			Dol.	4275
<u>ELECTRIC LOGS</u>				
GR-N-Guard & Caliper				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Vice-President
	Title
	September 2, 1977
	Date