

21-25-5E


WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Chesney No. 157

SEC. 21 T. 25 R. 5E
NW SW NE
940' N, 380' E of Center

Total Depth. 1494
Comm. 6-10-48 Comp. 6-22-48
Shot or Treated.
Contractor. B & R. Drlg.
Issued. 1-15-49

County. Butler
KANSAS



Elevation. 1355 Ind.

CASING:
10 3/4" 85' cem w/50 sx.
7" 1434' cem w/50 sx.

Init. Production. 106 bbls oil, 24 bbls
water, 24 hrs.
Figures Indicate Bottom of Formations.

lime	250
shale, lime	595
shale, shells	855
lime, shale	1150
shale, shells	1300
lime, shale	1434
sand	1494
total depth	

Tops:

Top Douglas Sand 1434
Base Douglas Sand 1478

STEEL LINE MEASURE:

1055-B. 1053.50
1361-1361
1423-B. 1423

No show in Oread Ls.

1434-38, G.S.O.
-43, S.S.O.
-73, G.S.O.
-78, S.O.
-87, N.S.O.

1434-38, Best Pay
1443-78, Best Pay

869' oil, trace water in
19 hrs. (fillup)
Not az. or shot.