

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


21-25-5E

Company - CITIES SERVICE OIL CO.
Farm - Chesney No. 158

SEC. 21 T. 25 R. 5E
SW SW NE
305' N & 397' E of Center

County. Butler

KANSAS



Total Depth. 11494'

Comm. 7-12-48

Comp. 8-3-48

Shot or Treated. None

Contractor. B. & R. Drlg. Co. (Drill in : C. L. Roberts)

Issued. 9-25-48

CASING:

10-3/4" 84' Cem. W/60 Sx.

7" 11432' Cem. W/50 Sx.

Elevation. 1367' *Ind.*

Production. 124 BO, 4 BW, 24 hrs.
N.P.O. Natural.

Figures Indicate Bottom of Formations.

lime	55
shale	70
lime	75
shale	86
lime	160
lime & shale	325
lime	500
shale	849
shale & sand	867
lime & shale	1320
lime	1322
lime & shale	1420
shale	1432
sand RTD	1435
sand & shale	1494
Total Depth	

Tops:

Oread Lime 1320
Douglas Sand 1432
Base Doug. Sand 1490

Steel Line Measure:

534' = 534'
819' = B 818'
1416' = 1416'

Cored 819-85
1310-56

1325-32 1/2 V. S. S. O.
1334 1/2-39 V. S. S. O.
-43 V. S. S. O.
-56 N. S. O.

1432 First free oil
1432-35 good show oil
1432-90 Best pay
Fill up 1025' oil, trace
wtr., 23 hrs.

Was not shot or acidized