

21-25-5E

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Chesney No. 155

SEC. 21 T. 25 R. 5E
NW NW SE
317' S & 260' E of Center

Total Depth. 2030'
Coring 1-23-48 Comp. 5-26-48
Sp. or Treated. Acidized
Contractor E. & R. Drlg. Inc.
Logging 6-26-48

County. Butler
KANSAS



CASING:
10 1/2" 82' Cem. W/ 65 Sx.
7" 1915' Cem. W/135 Sx.

Elevation. 1370 Ind.

Production. 55 BO, 18BW, 24 hrs.

Figures Indicate Bottom of Formations. P. O. After Az. from K.C. Ls.

lime	215
lime & shale	905
lime	1025
lime & shale	1205
lime	1290
lime & shela	1626
lime	1770
lime & shale	1912
lime	2006
shale	2018
lime	2030
Total Depth	

Steel Line Measure:
500 = 500
1087.68 = 1089.18
1522.73 = 1522.73
1894 = 1896

Top Lansing Ls. 1626
1644-57 S.S.O.
1670-77 S. O.
1685-91 S. O.
1736-46 S.S.O.
Base Lansing Ls. 1770
Top K. C. Ls. 1912
1919-24 S. O.
1924-46 F. S.O.
1953-58 F. S.O.
1978-84 S. S.O.
2018-26 V.S.S.O.

Tested 1/4 BO & trace wtr.
P. H. at Total Depth

Acidized W/5000 Gals. (5-31-48)