


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

21-25-5E

Company - CITIES SERVICE OIL CO.
Farm - Chesney No. 156

SEC. 21 T. 25 R. 5E
NW SW NE
950' N & 1060' E of Center

County. Butler
KANSAS



Total Depth. 1504'
Comm. 5-28-48 Comp. 6-17-48
Shot or Treated. None
Contractor. B. & R. Drilg. Co., Inc.
Issued. 8-7-48

CASING:

10-3/4" 80' Cem. W/65 Sx.
7" 1431' Cem. W/40 Sx.

Elevation. 1353 *ft.*

Figures indicate Bottom of Formations.

Production. 85 BO, 15 BW, 24 hrs.
N. P. O. Natural.

lime	35
shale	55
shale & shells	75
lime	82
lime & shale	200
lime	380
lime & shale	685
shale & shells	820
lime & shale	1431
sand	1504
Total Depth	

Steel Line Measure:
563 = B. 560
1410 = B. 1410

Top Douglas Sand 1431
1431-67 S. O.
-83 N.S.O.
1488-1504 N.S.O.
1431-67 Best Pay
Base Douglas Sand 1483

1100' oil, 0 wtr F.U. in 27 hrs.