

7-16-1W



Blackstone Drilling, Inc.

Box 455¹⁸⁴ 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

October 10, 1978

COMPANY: DALE REESE OIL COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: ODLE #1
 LOCATION: 990' WEL & 330' NSL SW/4 Sec. 7-16-1W,
 Saline County, Kansas
 COMMENCED: October 2, 1978
 COMPLETED: October 7, 1978
 ELEVATION:

0	to	121	Shale & Shells
121	to	800	Lime & Shale
800	to	1270	Shale & Lime
1270	to	2010	Lime & Shale
2010	to	2300	Shale & Lime
2300	to	2440	Lime & Shale
2440	to	2718	Lime
2718	to	2730	Mississippi
		2730	T. D.

Cut 12 1/2" hole to 119' and run 121' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 119'. Plug down at 11:45 A. M., October 2, 1978. Cut 7 7/8" hole to 2730'. Hole dry and abandoned. Set bottom plug at 120' with 15 sacks of cement. Filled with mud to 40'. Set top plug with 10 sacks of cement, 2 sacks in rathole. Plugging completed at 8:00 A. M., October 7, 1978. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas.

TOPS: LANSING - 2070' MISSISSIPPI - 2718'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Odle #1, located SW/4 Section 7-16-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

Charles D. Johnson Secretary-Treasurer