

State Kansas County Ellsworth

Company Gramehart-Miller Oil Co. Well No. 1


Farm Janssen "A"

Survey _____

Block No. _____ Sec. 24 Twp. 17S Range 8W

Co-Ord. C.P. 3150-75 Elev. 1696 KB

SE SW SW Rig #3 1691 Gr



50% - Chicago Group
50% - Gramehart-Miller

Geol: Vernon Hess

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line _____

990 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
		SPD 10-26-54
10-21		C&P
10-25		MIRT
10-26		Digging rat hole
10-27		8 5/8" @ 220' w/150 sx cem,
	4 c.c.	P.D. 4:30 P.M. 10-26-54
10-28	1445	Drlg
10-29	2117	Drlg
10-30	2608	Drlg
11-1	3067	Drlg

701168

Date	Depth	
11-2	2608	Heebner (-912)
	2736	Brown Lime (-1040)
	2758	Lansing (-1062)
	3220	Circulating for samples
11-3	3174	Viola (-1478)
	3221	Simpson (-1525)
	3272	Arbuckle (-1576)
	DST 3264-71', op 1 hr, cl 20 mins; rec 12' rotary mud. Wk Bl in 12 mins. BHP 780#.	
	3272	Circulating for samples (Will DST 3273-78)
11-4	DST 3273-78; rec 750' SW. Op 1 hr, Cl. 20 mins. R. Gd bl throughout test. IFP 0 - FFP 360# - BHP 1020#	
	3278	R.T.D. D&A