

State Kansas County Ellsworth
 Company G-M-R Oil Company Well No. 1
 Farm Sturn
 Survey _____
 Block No. _____ Sec. 36 Twp. 17S Range 10W
 Co-Ord. _____ Elev. 1779 R.B.

NE NE NW

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Spud 4-2-52
		8 5/8" @ 250' 2/150 sx.
4-4	1160	Drlg.
4-5	1747	"
4-6	2547	"
4-7	2900	"
4-8	2885	Brown Line
	2903	Lansing (-1124)
	Brks.	2927-31 N.S.
		2977-85 Some stn. & Odor

701174

Date	Depth	
		2993 - 90 ft. break
D.S.T.	2976-96	2976 * Open 1 hr. good blow
		Rec. 2640' gas - 270' fluid
		210' OCM, 60' GSW-BHP 1050#
D.S.T.		2996-99 Open 1 hr. blow 20"
		Rec. 80' MW & 120' SW-1100#
	3160	Drlg. sd 3223-27 BHP
4-9 D.S.T.	3190-3230	- Open 2 hrs. Rec. 150'
		G&OCM - 870# BHP Free oil
		in tool.
	3257	Arb. (-1478(
		Poor por. & sat.
	3262	T.D.
4-10		5½" @ 3259 -WOC
	3263	dp, dd. 250 acid. No show
	3270	dd. 400' water in hole
		L. W. Log - sq. open hole
Perf.	3251-57	N.S. 500 acid
"	3221-25	Trace oil
"	2992-96	2 BWPH - sq. with 100 sx.
		3000# Pres.
Perf.	2981-86	500 acid. 10 gal. oil & 35 gal. water per hr.
5-6		Pulled 2793' pipe.
		D & A