


20-16-1W

Total Depth. 1915' PB 1885'  
 Comm. 3-1-61 Comp. 3-16-61  
 Shot or Treated.  
 Contractor. Peters Drlg.  
 Issued. 3-10-62

County Saline  
 KANSAS



Elevation. 1324' DF

Production. 10 BOPD

CASING:  
 7" 208.20' cem w/45 sx.  
 4 1/2" 1916' cem w/45 sx.

Figures Indicate Bottom of Formations.

soil & clay	20
shale	130
shale & shells	208
lime	220
shale	233
lime	248
shale	258
lime	270
shale	283
lime	304
shale & shells	327
red bed	332
shale & shells	337
lime	386
shale & shells	391
lime	420
shale & shells	435
sandy lime	525
lime	536
shale	601
lime	646
red bed	651
lime	653
shale & shells	1180
lime	1202
Brown lime	1340
shale & shells	1409
broken lime	1468
shale & shells	1487
black shale	1529
lime	1582
lime & shale	1651
shale	1660
lime	1815
shale	1842
lime	1852
Core	1872
shale	1904
broken lime	1915 RTB
Total Depth	
Plugged back to 1885'	

TOPS: SCOUT  
 Douglas 1854

DST #1 1844-1872', op 6l mins, shut-in  
 15 min. Rec. 15' free oil, 91' slightly  
 oil cut mud. HP, in 985#, FP 20#,  
 FSIP 337#/15 mins, HP, out 945#.