

21-25-5E

**KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY**

508 EAST MURDOCK - WICHITA, KANSAS

**COMPANY** CITIES SERVICE OIL COMPANY

**SEC.** 21 **T.** 25 **R.** 5E

**FARM** Chesney **NO.** 166

**LOC.** NE SE NW

1020' N. 330' W. of Center

**TOTAL DEPTH** 1492

**COUNTY** Butler


**COMM.** 8-10-50

**COMP.** 8-23-50

**SHOT OR TREATED**

**CONTRACTOR** B & R Drilling Inc. ; Drill In: C. L. Roberts

**ISSUED** 1-27-51



**CASING**

10 3/4" 75' cem. w/50 sx  
7" 1461' cem. w/ 75 sx

**ELEVATION** 1360' R.T.B.

**PRODUCTION** 15 bbls. oil, 120  
wtr., 15 hrs.

FIGURES INDICATE BOTTOM OF FORMATIONS

Note: All measurements taken from R.T.B.  
(R.T.B. is 3.5' above grd.)

lime & shale	75
cement & lime	150
lime	375
lime & sand	410
lime & shale	1432
sandy shale	1452
shale	1458
sand & shale	1464, RTD
sand	1492
Total depth	

**Tops:**

Douglas sand 1461

**Steel Line Measure:**

1300=1300

1432=1432

1464=1464

**Remarks:**

V.S.S.O. 1461-64; S.O. 1464-72;

F.S.O. 1472-81; S.O. 1481-92;

First Free oil 1467-69'

Best Pay 1467-81'.

Shot w/30 qts. CME from 1472-1487

Cleaned out to T.D. 1492'.

Tested