

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- R. P. Baker
Farm- J. A. Wilson Estate No. 1

SEC. 22 T. 25 R. 5E
C SW SE

Total Depth. 2657'
Comm. 9-2-57 Comp. 9-29-57
Shot or Treated.
Contractor, R. P. Baker Drlg. Co.,
Issued. 11-16-57

County Butler

KANSAS



Elevation. 1338' RB.

Production. Dry

CASING:
8 5/8" 630' P. 7" 2545' P.
13 3/8" 920' P. 5 1/2" 2602' pulled 2310' 8"
10 3/4" 1570' P.
8" 2265' P.
Figures indicate Bottom of Formations.

cellar	8	lime	1175
lime 2 1/2 bw	70	shale	1190
shale	80	lime	1195
lime	115	shale	1210
red rock	120	lime	1215
shale	135	shale	1220
lime	165	lime	1225
red rock	175	shale	1260
shale	225	lime	1320
lime	230	shale	1365
shale	250	lime	1410
red rock	255	shale	1430
lime	260	lime	1445
shale	275	shale	1500
lime	285	sandy shale	1545
shale & shells	310	shale	1590
red rock	315	lime 1 bw	1610
lime	335	shale	1630
shale	385	lime	1645
lime 2/3 bw	390	shale	1695
shale	455	lansing lime	1700
shale & shells	480	1 bw 1745	1755
shale	595	lime	1835
lime	600	shale	1990
shale	630	lime	2090
brkn lime	640	shale	2095
2 bw 640	652	1/3 bw 2095-2100	
sand	658	lime	2115
sandy shale	666	shale	2120
shale	680	lime	2145
sand	688	shale	2232
shale	755	lime	2245
lime	775	shale	2268
shale	780	lime	2279
lime	790	shale	2284
shale	800	lime	2308
lime	835	lime	2320
shale	845	shale	2328
lime	850	lime	2332
shale	865	shale	2338
lime	870	lime	2355
shale	875	shale	2395
sandy shale	890	sand	2410
lime	895	shale	2435
sandy shale	915	brkn lime	2440
shale	955	sandy shale	2460
lime	970	shale	2470
shale	980	lime	2480
lime	990	shale	2500
shale	1015	lime	2510
lime 1 bw	1025	shale	2525
shale	1065	sandy lime	2438
lime	1095	cherty lime	2544
shale	1110	lime	2561
lime	1125	3 bw 2572-2576	
shale	1130	ssnd	2595
lime	1135	black shale	2600
shale	1150	gray lime	2610
lime	1155	green sandy shale	2625
shale	1165	HFW 2625-2630	

lime 2651
Total Depth 2657

Tops:
Lansing top 1695
Kansas City top 1990
Viola Top 2525
show of oil 2542
Simpson Top 2561
Arbuckle Top 2625

Hole reamed from 630-695
Light show of oil 640-46

2625
1336
- 1289