


LEADER OIL CO.
L.E.Walker No. 1.

SEC.17 T.32 R. 5 E
CNW SE

Total Depth. 3021'
Comm. 5-18-42 Comp. 6-5-42
Shot or Treated.
Contractor. Zephyr Drlg.Co.
Issued. 8-1-42

County. Cowley



CASING:
8 5/8" 92'
5 1/2" 2996'

Elevation.

Production. Pot.369 B.

Figures Indicate Bottom of Formations.

surface	118
lime	325
lime & shale strks	425
lime & shale	1715
lime & sdy shale	1889
shale & shells	1920
sand	2015
shale	2280
lime	2290
shale	2347
shale & sand	2365 Core #1
sand & shale	2383 Core #2
shale	2525
lime(K.C.)&shell breaks	2608
lime	2634
shale	2645
lime,shale,sand	2705
shale & lime	2727
lime	2760
lime & shale	2819
shale & lime	2835
lime & shale	2850
shale	3003
sand	3005
sdyl shale	3011
shale	3016
sand	3020
sand	3021
Total Depth.	

2835
1262

1573

Tops:
Stalnaker 1910
Layton 2359
K. C. lime 2523
Bartlesville 3000

sh oil 2365-83
good sh oil 3011-12

Shot w/40 Qts. 3005-21 6-6-42
Shot w/120 Qts.3007-21 6-16-42