

13-16-12W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company BLACK-MARSHALL OIL CO.
Farm A.Hoffman No. 6.

SEC. 13 T. 16 R. 12 W
SWc SE

Total Depth. 3323
Comm. 2-14-46 Comp. 3-21-46
Shot or Treated.
Contractor. Black-Marshall Oil Co.
issued. 4-13-46

County. Barton
KANSAS



CASING:
12 1/2" 476'P 7" 3200'P
10" 754' 5 1/2" 3318' Cem.
8" 2489'P

Elevation. 1884

Production. Phy.Pot. 196 B

Figures Indicate Bottom of Formations.

cellar	10	lime	2530
post	15	shale, shells	2550
shale	205	lime	2560
sand	215	shale	2620
red rock	310	lime	2625
shale	505	shale	2630
red rock	752	lime	2645
anhydrite	780	shale	2655
red rock	980	lime	2665
shale	1030	shale	2670
red rock	1095	lime	2675
shale	1195	shale	2695
salt	1415	lime	2945
shale, shells	1495	shale	2950
lime	1525	lime	2955
shale	1535	shale	2963
lime	1545	lime	2975
shale	1550	red rock	2985
lime	1565	shale	3038
shale	1570	lime	3045
lime	1610	shale	3055
shale	1625	lime	3117
lime	1665	shale	3120
shale	1675	lime	3140
red rock	1685	shale	3143
lime	1715	lime	3209
shale	1730	shale	3211
lime	1885	lime	3252
shale	1915	shale	3260
red rock	1920	lime	3283
lime	1950	shale	3290
red rock	1955	lime	3304
lime	1965	shale	3309
red rock	1970	lime	3313
lime	2040	conglomerate	3315
red rock	2047	lime	3320
lime	2085	no log	3323
shale	2115	Total Depth	
lime brkn	2125		
red rock	2130	All figures above	
shale	2140	subject to 5' up-	
lime	2160	the-hole correction	
shale	2180		
lime	2225	Tops- (uncorrected)	
shale	2235	Anhydrite	752
lime	2240	Lansing	3055
shale	2305	Base K.C.	3309
lime	2310	Arbuckle	3318
shale, shells	2350		
lime	2360	Shows of Water	
shale, shells	2385	5 BWH	206-15
shale	2435	4 BWH	600
shale, shells	2455	2 BWH	1815
shale	2480	1 1/2 BWH	2995
lime	2500	1 1/2 BWH	3155
shale	2510		

Show of Oil
Good show of free oil
120 ft. oil in 40 mins.
800 ft. oil in 2 hrs.