

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

Plotted
about 2:11
10-25-5E

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location SWc. NE NW


Sec. 10 T. 25 R. 5E

150' fr NL 1180' fr WL

Casing Record

County- Butler JUL 7 1929

20"	10" 20'	Farm- J. T. Nuttle	No. 1
15 1/2"	8 1/2" 210'	Company- Schreck & Lilly	
12 1/2"	65/8"	Contr.-	
	53/16"	Comm.- 5/29/29	Comp.- 6/12/29
Total Depth	703 1/2'	Shot	Quarts Between



Correspondence Regarding This Well Should Be Referred to

Elevation

Figures Indicate Bottom of Formations.

Initial Production 6 bbls. oil
and 10 bbls. water

Date Issued: 7/6/1929.

Formation	Depth
soil black soft	5
lime white hard	20
clay yellow soft	30
lime white hard	60
shale & shells white soft	80
lime white hard	110
10 bbls. fresh water per hr.	
shale blue soft	120
lime white hard	140
shale & shells white hard	150
red rock soft	162
lime white hard	195
shale blue soft	210
red rock soft	218
shale & shells hard	354
red rock soft	361
lime white hard	382
shale & shells black hard	470
lime white medium	495
shale blue soft	580
lime white hard	585
shale blue soft	600
lime shells hard & soft	650
shale 1 1/2" BW at 640'	670
sand oil soft	680
shale & shells black hard	695
sand and shale	703 1/2'
Total Depth	703 1/2'