

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

22-16-12W

Company - VICKERS PETROLEUM CO., INC.
Farm - Morgan "B" No. 6

SEC. 22 T. 16 R. 12W
SE NE NE

Total Depth. 3372½'

Comm. 4-18-48

Comp. 5-14-48


Shot or Treated.

Contractor.

Issued. 6-26-48

County. Barton

KANSAS



Elevation. 1934 *Ind.*

Production. Pot. Est 50 BOPH
25% Wtr.

CASING:

8-5/8" 450' Cem. W/185 Sx.

5-1/2" 3369' Cem. W/ 80 Sx.

Figures Indicate Bottom of Formations.

clay & limestone	250
shale	610
red bed	730
redbed & shale	825
anhydrite	850
shale	935
shale & shells	1260
salt & shale	1310
shale	1570
lime & shale	1655
lime brkn	1795
lime sdy	1905
lime & shale	1995
lime	2170
lime & shale	2740
lime	3034
shale & sand	3096
lime & shale	3109
lime	3357
red shale, chert sand	3369
dolomite RTD	3371
(All measures D.F.)	
Cable Tool Corr.	3371= 3369 CTD
D. D.	
very sdy dolomite	3372½'
Total Depth	

Swab 6½ BOPH 4 hrs S.S.W.

Tops: (D. F.)

Brown Lansing 3096

White Lansing 3109

Base Kansas City 3357

Arbuckle 3369