


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DEEP ROCK OIL CORP.
Farm - J.F. Robinson No. 19.

SEC. 16 T. 25 R. 5 E
S E NE SW
9 90' f NL 330' f EL SW $\frac{1}{4}$

Total Depth. 2484'
Comm. 5-27-44 Comp. 6-17-44
Shot or Treated.
Contractor. Rex & Morris Drlg. Co.
Issued. 9-2-44

County. Butler
KANSAS



CASING:
16" 100' P 8 5/8" 2040' P
13" 795' P 7" 2470' Cem.
10 3/4" 1550' P

Elevation. _____

Production. Swb 50 B.

Figures Indicate Bottom of Formations.

cellar	0-8	lime	1165	Viola Lime 2480-81
lime	35	lime brkn	1190	Show oil
shale	60	lime	1205	Viola Lime 2481-82
lime 2 BW 80-90	90	shale	1215	Hole filled up
shale	125	lime	1230	40' in 1 hr.
lime	130	shale	1235	Viola Lime 2482-83
shale	140	lime & shale	1245	No change
lime 1 BWPH 160-170	180	lime 1 BWPH 1265-75	1315	Viola Lime 2483-84
shale	195	shale	1365	Increase in oil-
red rock	200	lime	1415	hole filled 70'
lime	220	shale sdy smell gas	1420	in 30 min.
shale	235	lime	1435	
lime	245	shale	1455	6-18-44 Acidized
shale	255	lime	1460	w/500 gal - put
lime	260	shale	1470	in 56 bbl oil
shale	270	sand sh oil 1475-80	1515	ahead of acid &
lime	275	lime sdy	1533	14 bbl after
shale	285	shale	1580	acid
lime	290	lime	1585	
shale & shells	300	shale	1618	Hole drilled with
lime	325	lime	1630	cable tools.
shale	340	lime	1680	
lime 1 BW 350-65	365	shale	1850	
Total 2 BWPH		lime	1850	
shale	370	Smell oil 1690-95; 2 1/2 BWPH		
lime	380	1780-1800; Total 4 BWPH		
shale	390	shale	1995	
lime brkn	415	lime	2085	
lime	480	shale blk	2090	
shale	490	lime	2115	
lime	498	lime brkn	2125	
shale	530	shale	2135	
shale & shells	590	lime	2140	
shale	645	shale	2225	
lime brkn & sand	660	lime	2275	
show of oil		shale	2305	
shale	682	caving 2260-2305		
lime sdy & oil 1 BWPH	690	shells-shale	2335	
shale	697	lime	2355	
lime	705	shale	2385	
shale	715	shale dk gy	2390	
shale sdy	750	sand blk Asphaltic	2398	
shale & shells	785	shale dk	2410	
lime	810	lime shells	2411	
shale	815	shale green	2419	
lime	855	shale gy	2422	
shale & shells	880	sand wh	2427	
shale	970	lime sdy wh	2428	
lime brkn	990	shale green	2441	
shale	1000	shale dk gy	2455	
lime	1010	shale	2470	
shale	1040	shale blk & little gy		
lime	1045	& green shale	2480	
shale	1075	lime sh oil	2481	
lime	1105	lime free oil	2482	
shale	1120	lime brwn hole filled		
lime	1125	70' in 1/2 hr	2484	
lime smell oil 1125-30	1140	Total Depth		
shale	1150			