


Company - DEEP ROCK OIL CORP.
Farm - L.W. Robinson No. 47.

SEC. 16 T. 25 R. 5 E
NWc SW

Total Depth. 2600' PB 2575'
Comm. 11-3-43 Comp. 1-6-44
Shot or Treated.
Contractor. Rex & Morris Drlg. Co.
Issued. 4-22-44

County. Butler
KANSAS



CASING:
16" 216' 8 5/8" 2040' P
13" 855' P 7" 2440' Cem.
10 3/4" 1583' P 5 1/2" 2572' P 2412'

Elevation. _____

Production. Swbd 125 B.

Figures Indicate Bottom of Formations.

cellar	8	lime	1000	lime & sand	2598
clay & lime	25	shale	1010	sand HFW	2600
shale	40	lime	1015	Total Depth.	
lime	55	shale	1018	Hole plgd back w/rock & cement	
lime sft	80	lime	1025	to 2575	
lime	100	shale	1080		
shale	115	lime	1115	chert, sm sh oil	2430-40
lime	120	shale	1125	chert hd, no inc.	2440-52
shale	145	lime	1155	chert, med hd, inc. oil	2452-56
red rock	150	shale	1170	chert hd, no inc.	2456-59
shale	195	lime	1180	chert med sft, sm inc.	2459-69
red rock	200	shale	1185	chert sft coarse, hole	
lime	205	lime brkn	1205	fills up about 200'	
shale	220	lime	1220	in 8 hrs	2469-78
lime	225	shale	1230	chert sft wh, no inc.	2478-97
shale	235	lime	1250	shale green	2497-2507
lime	240	lime & shale brkn	1265	shale dk	2507-15
shale	320	lime (sh gas 1285)	1335	at this depth well shot w/	
lime	325	shale	1385	5 qts & 20 qts as shown be-	
shale & shells	340	lime	1430	low & tested-pmpd 15 bbls	
red rock	345	shale	1435	24 hrs	
shale	350	lime (little gas 1470)	1455	shale dk	2515-68
lime	410	shale	1470	lime Viola med, stain	
shale	415	shale sdy	1475	of oil	2568-72
lime hd	425	lime	1480	lime Viola hd	2572-78
shale	430	shale sdy	1515	lime sdy, rainbow oil	2578-85
lime	450	sand HFW 1520	1565	shale green	2585-90
shale	455	shale sdy	1570	dolomite lime & shale	2590-98
lime	470	shale	1612	Wilcox sand, sulphur	
shale	475	lime	1617	wtr	2598-2600
lime	485	shale	1640	plugged back w/rock &	
shale	490	lime	1655	cement	2600-2575
lime	500	shale	1705		
shale	545	lime	1725	12-3-43 5 qts, 2456-63 no test	
shale & shells	560	shale	1730	12-4-43 20 qts, 2455-65 pmpd	
shale blk	580	lime (3BW 1740-50)	1862	15 bbl 24 hrs	
lime	585	smell oil 1780-90			
shale	590	3BW 1800, total 6BW			
lime	600	shale	2010	Left 160' of 5 1/2" in hole for	
shale, lime shells	630	lime (1/2 BWP 2095-2105)	2110	liner-gun perf. liner from	
shale (sh oil 655)	653	shale	2112	2450-60 w/16 shots & 2562-70	
lime sdy	660	lime	2138	w/24 shots	
shale	670	shale	2145		
lime sdy	680	lime	2165		
shale	700	shale	2245		
lime brkn	710	lime brkn	2255		
shale	750	shale	2290		
shale sdy	760	lime	2300		
shale	770	shale	2325		
lime	778	lime brkn	2335		
shale	790	lime	2370		
lime	800	shale	2425		
shale	805	lime (sm sh oil	2430		
lime	810	chert 2430-40)	2497		
shale	825	free oil 2450-60			
lime	860	shale green	2499		
shale & shells	880	shale (caving 2545)	2568		
shale	915	lime	2585		
lime	920	shale green	2590		
shale	980	shale & shells	2596		