

22-16-12W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - C. U. BAY
Farm - Riemann "C"

No. 1

SEC. 22 T. 16 R. 12W
CE₂¹ NE SE

Total Depth. 3373'

Comm. 2-24-48

Comp. 5-1-48


Shot or Treated.

Contractor. Gabbert & Lindas Drlg. Co., Inc.

Issued. 5-29-48

County. Barton

KANSAS



Elevation. 1926.9nd.

Production. Pot. 69.08 BO/8 hr.
no water.

CASING:

8-5/8" 281' Cem. W/ 150 Sx. (RB)

5" (RB) 3369' Cem. W/ 75 Sx.

Figures Indicate Bottom of Formations.

sand & shale	281
shale & sand	550
red bed & shale	620
shale & shells	820
anhydrite	835
red bed & shale	1125
shale & shells	1195
shale & salt	1330
shale	1420
shale & shells	1675
shale & lime	1915
lime	2035
lime brkn	2125
lime brkn	2235
shale & lime	2455
lime brkn	2708
lime	2867
shale & lime	2970
lime	3014
lime & shale	3100
lime	3371
sand	3373
Total Depth R.B.	

Tops:

Br. lime	D.F.	3087
Kansas City	D.F.	3101
Gotham sand	D.F.	3364

Slight show oil 3114-18

very small show oil 3189-93

good por. & good show oil 3368-70

D.P. - Cleaned out to RTD - 3373

Very small show oil.

D.D. - 3376, no increase

Cuts. 3376-70

swbd. 20 BOPH, no wtr.